



**NATIONAL INSTITUTE OF TECHNOLOGY  
HAZRATBAL, SRINAGAR- 190006 (J&K)**  
(Planning & Development Wing)  
Tel: 0194-2102157 Fax: 0194-2420475

E- Tender No. 09 of 2021

For & on behalf of Chairman Board of Governors NIT Srinagar, e-tenders (**in Two Cover System**) are invited from **Electric Contractors** registered with state PWD, CPWD, MES for the below mentioned work:-

S. No	Particulars of Items	Contract value	Time period	Class of contractor	Cost of T.D
01	Electrical Stage	Rs. 60.00 Lacs	01-04-2021 to 31-03-2022	A & B (Electrical )	Rs. 1000/-

**Bidders are requested to Submit the online bids on E-tendering portal.**

Website for online bid submission : <https://mhrd.euniwizarde.com>

Cost of Tender documents: - 50/- to be paid online mode only

**Terms & Conditions:-**

1. The Bidding documents Consisting of qualifying information, eligibility criteria, specifications, Drawings, bill of quantities (B.O.Q), Set of terms and conditions of contract and other details can be seen/downloaded from the NIT website [www.nitsri.ac.in](http://www.nitsri.ac.in) as per schedule of dates given below:-

1	Date of Issue of Tender Notice	20-05-2021
2	Period of downloading of bidding documents	22-05-2021
3	Bid submission <b>Start Date</b>	22-05-2021
4	Bid submission <b>End date</b>	17-06-2021 till 23:59
5	Date and time of opening of bids ( <b>Online</b> )	<b>At 11:00 A.M in the office of Dean P&amp;D wing on 17-06-2021</b>

2. Bids must be accompanied with cost of Tender document in shape of **NIT, Chest receipt/( Mentioning therein Nomenclature of the work and Advertised Cost)** in favour of **Dean P&D Wing, NIT, Srinagar(tender inviting authority) and** the cost of downloaded tender document as shown above in the table should be deposited in J&K Bank A/C No: 039101010000106.
3. The date and time of opening of Bids shall be notified on Web Site **www.nitsri.ac.in** and conveyed to the bidders automatically through an e-mail message on their e-mail address. The **bids of Responsive bidders** shall be opened online on same Web Site in the Office of **Dean P&D Wing NIT, Srinagar (tender receiving authority)**.
4. The bids for the work shall remain **valid for a period of 120 days from the date of opening of Technical bids**
5. The earnest money shall be forfeited, If:-
  - a. Any bidder/ tenderer withdraw his bid/ tender during the period of bid validity or makes any modifications in the terms and conditions of the bid.
  - b. Failure of Successful bidder to furnish the required performance security within the specified time limit.
  - c. Successful bidder to execute the agreement within 28 days after fixation of contract.
6. **Instruction to bidders regarding e-tendering process.**
  - a. Bidders are advised to download bid submission manual from the "Downloads" option as well as from "Bidders Manual Kit" on website **www.nitsri.ac.in** acquaint bid submission process.
  - b. To participate in bidding process, bidders have to get 'Digital Signature Certificate (DSC)' as per Information Technology Act-2000. Bidders can get digital certificate from any approved Vendor.
  - c. The bidders have to submit their bids online in electronic format with digital Signature. No bid

will be accepted in physical form.

- d. Bids will be opened online as per time schedule.
- e. Bidders must ensure to upload scanned copy of all necessary documents with the bid.
- f. **Bidders must ensure to upload scanned copy of all necessary documents with the technical bid.**

**Note: - Scan all the documents on 100 dpi with black and white option.**

7. Any item or items of work beyond the allotted items necessitated at site if any shall be also paid on allotted appreciation/depreciation on the Estimated Rate.
8. Bidders are advised to use "**My Documents**" area in their user on E-Wizarde e-Tendering portal to store such documents as are required.
9. **Instructions to Bidder (ITB)**
  - a. All bidders shall upload the following information and documents along with qualification criteria / qualification information with their bids:-
  - b. **Copies of original documents defining constitution/ legal status, place of registration and principal place of Business with Cell No. and Correspondence address.**
  - c. **Treasury Challan/CDR/FDR**
  - d. **Scanned Copy of PAN Card**
  - e. **Scanned Copy of GSTIN Registration and latest clearance certificate FORM GST-3B i.e. latest clearance certificate FORM GST-3B of the preceding Month to the issued of NIT.**
10. All documents relating to the bid shall be in the English Language.
11. **Bidder must ensure to upload scanned copies of all necessary documents including earnest money and tender documents fee in terms of soft copies with technical bid. No document (s) which has /have not been uploaded shall be entertained in the form of hard copy. However, in case of any clarification the bidders shall have to produce original documents in support of soft copies if need arises**
12. The date of start of the work shall be reckoned from the 3<sup>rd</sup> day of issuance of LOI/Contract allotment as the case may be.
13. **Penalty for delay in completion:-**In case of delay in completion of work beyond stipulated period of completion, penalty upto Rs. 200/- per day shall be imposed.
14. **The tender receiving authority reserves the right to accept or reject any tender or all tenders without assigning any reason thereof.**
15. **Restoration of work:-** On completion of contract the contractor shall be responsible to remove all unused material and restore all work in its original position at his own cost.
16. **Traffic regulations:-**The contractor is bound to adhere to traffic regulations as is applicable from time to time and ensure arrangements of smooth regulation of traffic during execution of work.
17. **Defect Liability period:-** The DLP shall be Calculated from date of certified completion of work and period **shall be 06 months.**The defects noticed in the work during execution or D.L.P. shall be corrected by the Contractor within the length of time specified by the Engineer. If the contractor does not correct the defects pertaining to D.L.P. to the satisfaction of the Engineer within the time specified, the Engineer will assess the cost of having the defects corrected and contractor will pay this amount on correction of defects.
18. The date of start of work shall be reckoned within seven days from the date of issuance of allotment/ Letter of intent. In case the agency fails to execute the work, the deposits in the shape of CDR and Additional performance guarantee shall be liable for forfeiture besides initiating other punitive actions against the defaulter without serving any notice.
19. **Tests:-**The contractor shall be solely responsible for carrying out the mandatory tests required for the quality control at his own cost.
20. **Termination: -** The employer may terminate the contract if the contractor causes a fundamental breach of the contract.
21. **Court's Jurisdiction: -** In case of any dispute/differences between contractor and department the Jurisdiction shall be union territory of J&K.
22. ***It is not mandatory for the department to execute the works upto the tune of Rs. 60.00 lacs & minor works shall be executed as per requirement.***
23. *The Electrical Stage 2021 -2022 shall remain in force till 31st of March 2022.*
24. *Individual work shall not exceed Rs.8,00,000 & time limit of individual work shall be as under:*

**i) For the work of up to Rs 2, 00, 000 ... 10 days**

**ii) For the work from Rs 2, 00, 000 up to Rs. 4, 00,000 ... 20 days**

**iii) For the work from Rs 4, 00, 000 up to Rs. 6, 00,000 ... 25 days**

**iv) For the work from Rs 6, 00, 000 up to Rs. 8, 00,000 ... 30 days**

*If the work is not executed within specified time, the penalty @ Rs. 200/- per day shall be imposed. Duration will be counted after 2 days from the date of issue of written job order.*

**25. Maximum Limit & Individual limit of the stage shall be as under :-**

<i>Maximum limit of contract</i>	<i>Maximum limit for Individual work</i>
<i>Rs. 60.00 lacs</i>	<i>Rs. 8.00 lacs</i>

**26.** The contractor who will participate in the tendering shall have to fill declaration form which is annexed with the NIT.

**27.** After opening of tender the lowest tenderer has to submit earnest money of the 2% of the tendered cost within 7 days from the issue of the letter and award of contract shall be accordingly issued in favour of L1.

**28. Other Conditions.**

- If any omission is found in the specification / rate of item or there is an any typographical error in the rate/item, the same shall be read as per approved estimate*
- The supply if found defective /not as per approved specifications, the item will not be accepted and will have to be replaced at the risk & cost of allottee.*
- The rates should be written clearly and legible both in words and figures and avoid corrections. Further all rates should be covered with transparent tape.*
- Any tenderer quoting "Free of Cost" for any item of work, the tender shall be rejected.*
- The tenderer quoting "Rebate" on comparative cost or on item of rate will be rejected. Contractor should thus adjust amount within the quoted rate structure.*
- The splitting of quantity of any item i.e. quoting of more than one rate for the item is not accepted.*
- The competent authority reserves the right to reject any tender without assigning any reason thereof.*

*Dean P & D*

*No.NIT/P & D /21/212*

*Dt. 20-05-2021*

**TENDER DOCUMENT OF ELECTRIC STAGE 2021-22**

The intending tenders are requested to quote so much percentage above /below the proposed rates in the following manner:-

<i><b>S.No.</b></i>	<i><b>Particulars of item</b></i>	<i><b>Rate to be quoted by the Contractor</b></i>
<i><b>01</b></i>	<i><b>The contractor may quote single percentage of rate above or below (Appreciation/depreciation) neatly in figures as well as in words to all items of CPWD DSR 2018 Electric under various heads and for the items which are not covered in DSR 2018 placed below.</b></i>	

<b>S.No</b>	<b>Particulars</b>	<b>Unit rate</b>										
	<b>Computer / Heating / Charging/ Internet Points</b>											
1)	<p>P/F of Computer board point of Modular switch/socket including switch Box, 8 module plate, 8 Modular Base, 8 Modular Metal Boxes and cover plate etc as required. The details of the switch /Sockets are as follows:</p> <table border="0"> <tr> <td>1. 15 Amp Switch</td> <td>1 No.</td> </tr> <tr> <td>2. 15 Amp Socket (Universal)</td> <td>1 No.</td> </tr> <tr> <td>3. 6A/10 A, 5-pin Socket</td> <td>2 Nos.</td> </tr> <tr> <td>4. Indicator</td> <td>1 No</td> </tr> <tr> <td>5. 6A 2 pin socket</td> <td>1 No.</td> </tr> </table>	1. 15 Amp Switch	1 No.	2. 15 Amp Socket (Universal)	1 No.	3. 6A/10 A, 5-pin Socket	2 Nos.	4. Indicator	1 No	5. 6A 2 pin socket	1 No.	<b>1,450.00</b>
1. 15 Amp Switch	1 No.											
2. 15 Amp Socket (Universal)	1 No.											
3. 6A/10 A, 5-pin Socket	2 Nos.											
4. Indicator	1 No											
5. 6A 2 pin socket	1 No.											
2)	<p>P/F of Computer board point of Modular switch/socket including switch Box, 12 module plate, 12 Modular Base, 12 Modular Metal Boxes and cover plate etc as required. The details of the switch /Sockets are as follows:</p> <table border="0"> <tr> <td>1. 15 Amp Switch</td> <td>1 No.</td> </tr> <tr> <td>2. 15 Amp Socket (Universal)</td> <td>2 No.</td> </tr> <tr> <td>3. 6A/10 A, 5-pin Socket</td> <td>3Nos.</td> </tr> <tr> <td>4. Indicator</td> <td>1 Nos.</td> </tr> </table>	1. 15 Amp Switch	1 No.	2. 15 Amp Socket (Universal)	2 No.	3. 6A/10 A, 5-pin Socket	3Nos.	4. Indicator	1 Nos.	2,350.00		
1. 15 Amp Switch	1 No.											
2. 15 Amp Socket (Universal)	2 No.											
3. 6A/10 A, 5-pin Socket	3Nos.											
4. Indicator	1 Nos.											
3)	Supplying & fixing following modular switch of 15/16 Amp, Socket outlet of 6 pin 15/16 Amp and GI metal box along with modular base & cover plate of 3 module (100mm × 75mm ) for modular switches in recess including connections etc as required. complete the job in all respects.	<b>350.00</b>										
4)	Supplying & fixing following <b>modular switch of 25 Amp</b> , Socket outlet of <b>3 pin 25 Amp</b> and GI metal box along with modular base & cover plate of 3 module (100mm × 75mm ) for modular switches in recess including connections etc as required. complete the job in all respects.	<b>550.00</b>										
5)	Supplying & fixing following <b>modular</b> Socket outlet of <b>3 pin 25 Amp having modular box with mini MCB of 25 A "C" curve, 25A Top</b> and GI metal box along with modular base & cover plate of 3 module (100mm × 75mm ) for modular switches in recess including connections etc as required. complete the job in all respects.	<b>600.00</b>										
6)	Supplying and fixing 20 A, 240 V, Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith/including 20 A "C" curve, DP MCB (20A 1P+N+E P&S, Ref: A9HMS220). The Metal clad includes Plug & Socket Unit with Electra Plug & Socket and provision to mount modular protection devices to feed the end load directly as required.	2,750.00										
7)	Supplying and fixing 30 A, 415 V, <b>Four pole</b> Industrial type socket outlet, with 4 pole and earth, metal enclosed plug top along with 30 A "C" curve, <b>Four Pole MCB</b> , in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	4,200.00										
8)	Supplying & Fixing of Charging Point of following <b>modular switch of 16 Amp, 2 No of Socket outlet of universal type 3-pin 6 Amp, Indicator</b> and GI metal box along with modular base & cover plate of 6 module for modular switches in recess including connections etc as required. Complete the job in all respects.	<b>1150.00</b>										

9)	P/F 5 KVA wall mount, copper wind, air cooled Auto Voltage Regulator of Global / IFB/ or equivalent make with design voltage range of (I/P 90-290V and O/P 200-290V). Complete in all respect.	<b>12,000.00</b>
10)	P/F of earthing to main board which includes digging of earth pit upto 8', filling of earth pit with charcoal, salt etc. of required quantity and fixing of copper plate of 600mm x 600mm x 5mm dimensions and provide masonry enclosure with plate having locking arrangement and water pipe of 2.7 meter long cover long etc with charcoal/coal and salt as required. The job includes 0.5 inch copper strip to be earthed with sub-main LT panel/distribution box. Complete in all respects.	<b>15,000.00</b>
11)	P/F of Maintenance free Chemical Earthing using copper Electrode of size 76 mm dia, 03 meter long connected with 50X6 mm Copper internal strip complete with excavation, civil works, cast iron cover with back fill compound along with <b>60 kg bag of Back fill compound/SOR Compound (highly conductive, non corrosive moisture retaining chemical)</b> complete. The voltage between Neutral & Earth not to exceed 0 volts & IR value less than 1 ohm. The earth resistance shall be as per IS 3043. Copper strip of size 32 mm X 5 mm be connected to main Distribution board.	30,000.00
12)	P/F of Maintenance free Chemical Earthing using G.I Electrode of size 76 mm dia, <b>3 meter long connected with 50X6 mm G.I</b> internal strip complete with excavation, civil works, cast iron cover with back fill compound along with <b>60 kg bag of Back fill compound/SOR Compound (highly conductive, non corrosive moisture retaining chemical)</b> complete. The voltage between Neutral & Earth not to exceed 0 volts & IR value less than 1 ohm. The earth resistance shall be as per IS 3043. G.I strip of size 32 mm X 5 mm be connected to main Distribution board.	12,500.00
13)	P/F of UTP Cat-6e cable of Dlink make in 2mm PVC pipe of Alba/Plaza make of suitable size. Complete in all respect.	85/mtr
14)	P/F of computer socket-RJ45 with key stone/face plate for internet connection of Dlink/legrand make with suitable connections. Complete in all respects.	<b>750.00</b>
15)	P/F of Telephone socket-RJ11 with key stone/face plate for telephone connection of Dlink/legrand make with suitable connections. Complete in all respects.	370.00
16)	Supply, installation, testing, and commissioning of IP 65 LED street light fitting having system lumen output of 7000 lumens and system efficacy better than 80 lumens per watt with pressure die cast aluminum alloy body and life expectancy of 50,000 hrs @ L70, PF better than 0.9 CRI better than 70, TDH less than 15% complete with all accessories suitable for vertical/horizontal mounting on pole complete with connections etc as required. ( Make: Trilux / Phillips/ schneider / zumtobell)	<b>15,000.00</b>
17)	P/F of wall light with following specifications:- Model :- OMEGA Type: - 929689640802. Color: - White and Silver. Material: - ABS & Polycarbonate. Lamp base & wattage:- 1pcs Essential 18W B22 CDL Incl. Make: - Philips or equivalent Bajaj or HPL.	<b>950.00</b>
18)	P/F of Inverter technology <b>O General 1.5 Ton 5 Star Split AC with following Specifications.</b> <ul style="list-style-type: none"> <li>• <b>Type: - Split AC, Wall Mounted, Noise 26dB, refrigerant 410a</b></li> <li>• <b>Capacity: - 1.80 Ton.</b></li> <li>• <b>Make :- Daikin /IFB</b></li> <li>• <b>power input 1480 w, operating current 6.6 amps, cooling capacity 5200</b></li> </ul> Other Features: - Anti bacteria Filter, Jet Cool, Auto Start, Timer, and Sleep Mode. Complete in all respects including copper pipes, 4-core electric cable, MS stand, drain pipe and 5 KVA wall mount, copper wind, Stabilizer of O General or equivalent make (I/P 90-290V and O/P 200-240V). Complete in all respects.	98,500.00
19)	P/F of Inverter technology based Air Conditioner HVAC (Hot and Cold) with following Specifications:- <ol style="list-style-type: none"> <li>1. Company fitted Heat Convactor.</li> <li>2. Type: - Split AC, Wall Mounted.</li> <li>3. Capacity: - 1.80 Ton.</li> <li>4. Make :- Daikin /IFB</li> <li>5. Voltage: - 230 Volts.</li> </ol>	<b>95,000.00</b>

	Other Features: - Anti bacteria Filter, Jet Cool, Auto Start, Timer, and Sleep Mode. Complete in all respects including copper pipes, 4-core electric cable, MS stand, drain pipe and 5 KVA wall mount, copper wind, Stabilizer of Global / Alba/V-Guard/ make(I/P 90-290V and O/P 200-240V). Complete in all respects.	
20)	<p>P/F of Inverter technology based Air Conditioner HVAC (Hot and Cold) with following Specifications:-</p> <ol style="list-style-type: none"> <li>1. Company fitted Heat Convector.</li> <li>2. Type: - Split AC, Wall Mounted.</li> <li>3. Capacity: - 1.50 Ton.</li> <li>4. Make :- Daikin /IFB</li> <li>5. Voltage: - 230 Volts.</li> </ol> <p>Other Features: - Anti bacteria Filter, Jet Cool, Auto Start, Timer, and Sleep Mode. Complete in all respects including copper pipes, 4-core electric cable, MS stand; drain pipe and 5 KVA wall mount, copper wind, Stabilizer of Global / Alba/V-Guard (I/P 90-290V and O/P 200-240V)make. Complete in all respects.</p>	<b>82,000.00</b>
21)	Supply and Installation of Remote Controlled wall mounted blower (Humidifier heater) of 2000 Watt , 240volt. <b>(Make: Warmax /bajaj)</b>	<b>6,000.00</b>
22)	Supply and Installation of Remote Controlled wall mounted blower (Humidifier heater) of 2000 Watt , 240volt. <b>(Make: Usha only)</b>	<b>8,500.00</b>
23)	<p>Providing, installation, Testing and commissioning of 42 " Widescreen LED TV of SAMSUNG/LG or equivalent make including HDMI to DVI signal output cable with following specification.</p> <ol style="list-style-type: none"> <li>1. Aspect Ratio 19:9</li> <li>2. Resolution 1920 x 1080</li> <li>3. Video Input RGB, HDMI/DVI</li> <li>4. Digital (connectivity) HDMI/DVI with HDCP</li> <li>5. Audio RGB/DVI Audio, Composite Audio(RCA)</li> <li>6. Analog Composite(BNC), RGB</li> <li>7. Audio Power 20W(10W x 2)</li> <li>8. Source Selection HDMI/DVI, RGB, AV</li> <li>9. Power Consumption(Normal) 220W</li> </ol>	<b>45,000.00</b>
24)	<p>Providing, Installation, Testing and Commissioning of 65" LED TV of Samsung or equivalent make with HDMI, Wi-Fi facility and with following specifications.</p> <ol style="list-style-type: none"> <li>1. Brand Name: Samsung, sony,</li> <li>2. Smart functionality: Yes</li> <li>3. Built-in Wi-Fi: Yes</li> <li>4. Dimensions (W×H×D): 57.3"×35.8"× 14.5"</li> <li>5. Display Image: 65"</li> <li>6. Speaker count: 2</li> <li>7. Resolution: 1920 × 1080 pixels</li> <li>8. HDMI port: 4</li> <li>9. USB Port: 3</li> <li>10. Power supply: 100-240V, 50-60Hz</li> </ol>	<b>85,000.00</b>

25)	Providing, installation, Testing and commissioning of 55" Full HD LED TV of SANSUI/LG or equivalent make with internet, HDMI and with following specifications. <ol style="list-style-type: none"> <li>1. Display Features: FULL HD</li> <li>2. Screen Size: 55"</li> <li>3. Connectivity: HDMI, USB Ports.</li> <li>4. Resolution: 1920×1080 pixels</li> <li>5. No. of Selectable Picture Modules: 5</li> <li>6. Audio Output: 20W( 10W×2 )</li> <li>7. No. of Speakers: 2</li> <li>8. Power Consumption:135 Watt.</li> <li>9. Power Supply: 100-240V, 50-60 Hz</li> </ol>	<b>65,000.00</b>
26)	Providing, installation, Testing and commissioning of 32" HD LED TV of SAMSUNG / LG or equivalent make with HDMI and with following specifications. <ol style="list-style-type: none"> <li>1. HD Resolution: 1366 × 768</li> <li>2. HDMI Ports: 2</li> <li>3. USB Port: 1</li> <li>4. PMI ( Picture Mastering Index): 300Hz</li> <li>5. Built-in Speakers: 2</li> <li>6. LED Display</li> <li>7. Supply AC: 100-220V, 50-60 Hz</li> </ol>	<b>35,000.00</b>
27)	Providing, installation, Testing and commissioning of 55" Full HD ANDRIOD LED TV with following specifications. <ol style="list-style-type: none"> <li>1. Display Features: LED FULL HD</li> <li>2. Screen Size: 55"</li> <li>3. Connectivity: ETHERNET INPUTS : 1 NO 4 HDMI Ports WIFI CONNECTIVITY RF(provision for Cable connection)</li> </ol> INTERNET BROWSER Yes(Opera) APPLICATION STORE Yes (Google Play Store) One-touch mirroring, Screen mirroring (Miracast™), Google™ Cast, Video & TV SideView (iOS/Android), Photo Sharing Plus <ol style="list-style-type: none"> <li>4. Resolution: 1920×1080 pixels</li> <li>5. No. of Selectable Picture Modules: 5</li> <li>6. Audio Output: 20W( 10W×2 )</li> <li>7. No. of Speakers: 2</li> <li>8. Power Consumption:135 Watt.</li> <li>9. Power Supply: 100-260V, 50-60 Hz</li> </ol>	<b>87,000.00</b>

28)	<p>Providing, installation, Testing and commissioning of 49" Full HD ANDRIOD LED TV with following specifications.</p> <ol style="list-style-type: none"> <li>1. Display Features: LED FULL HD</li> <li>2. Screen Size: 49"</li> <li>3. Connectivity: ETHERNET INPUTS : 1 NO 4 HDMI Ports WIFI CONNECTIVITY RF (provision for Cable connection)</li> </ol> <p>INTERNET BROWSER Yes(Opera) APPLICATION STORE Yes (Google Play Store)</p> <p>One-touch mirroring, Screen mirroring (Miracast™), Google™ Cast, Video &amp; TV SideView (iOS/Android), Photo Sharing Plus</p> <ol style="list-style-type: none"> <li>4. Resolution: 1920×1080 pixels</li> <li>5. No. of Selectable Picture Modules: 5</li> <li>6. Audio Output: 20W( 10W×2 )</li> <li>7. No. of Speakers: 2</li> <li>8. Power Consumption: 135 Watt.</li> <li>9. Power Supply : 100-260V, 50-60 Hz</li> </ol>	65,000.00
29)	Supply, Installation, Testing and Commissioning of multimedia LED projector Epson EB-S31 3LED SVGA projector Brightness 3200lm with HDMI Port (3200 lumens) Connectivity including providing & fixing Ceiling Mount Kit Square and installing the projector on ceiling in a well protected iron cage of suitable size . The job includes providing & fixing 20 meter HDMI/VGA Cable with connectors using PVC conduit/channel. Complete in all respects.	42,000.00
30)	Supplying & fixing white wall mounted screen (6' x 8') for the multimedia LED projector, pull down type.	10,000.00
31)	P/F of high lumen LED 6500k, 120lm/w wall mounted led batten, extruded aluminum heat sink provided for efficient heat dissipation & integrated electronic driver including earthing point. Complete in all respects. (Make Phillips --+TYPE: BN 100C LED40S-6500 PSU L120 GR- (4ft)	2,400.00
32)	P/F of high lumen LED 6500k, 120lm/w wall mounted led batten, extruded aluminum heat sink provided for efficient heat dissipation & integrated electronic driver including earthing point. Complete in all respects. (Make Phillips TYPE: BN 021C- LED20S PSU CWGR S2 (4ft)	1,050.00
33)	Supply, Installation, Testing and Commissioning of <b>M1/M1E portable LED projector of resolution 854*480WVGA of 450 Lumens</b> , contrast ratio: 120000:1 with HDMI Port Connectivity. The back up life of battery must be atleast 2 hrs. The job includes providing & fixing 20 meter HDMI/VGA Cable with connectors using PVC conduit/channel. Complete in all respects.	45,000.00
34)	<b>P/F of Tall Tubular 180Ah Battery, 12 V</b> Tubular battery of Exide, Amaron, or equivalent Battery including suitable plastic trolley along with brass terminals in all respects. <b>3 years warranty</b>	19,500.00
35)	<b>P/F of Tall Tubular 200Ah Battery, 12V</b> Tubular battery of Exide/Amaron, or equivalent make Battery including suitable plastic trolley along with brass terminals in all respects. <b>3 Years warranty</b>	21,500.00
36)	P/F of 150AH 12V Tubular battery of Exide/ Amaron, or equivalent make Battery including suitable plastic trolley along with brass terminals in all respects.	14,500.00
37)	P/F of 1100 VA sine wave Inverter of Luminous/Amaron/Exide with all accessories.	8,300.00



38)	P/F of 1600 VA sine wave Inverter of Luminous/Amaron/Exide with all accessories.	13,500.00
39)	<p><b>P/F of 2500 VA, 24/36 Volt sine wave Inverter</b> of with following specifications:</p> <ul style="list-style-type: none"> <li>• MICRO-CONTROLLER BASED Intelligent Control Design.</li> <li>• Display Indications (Status &amp; Fault)</li> <li>• CCCV Technology with Auto Trickle Mode</li> <li>• Smart Overload Sense and Short Circuit Protection</li> <li>• Battery State Monitoring</li> <li>• Easily Serviceable</li> <li>• Multi Stage Battery Charger</li> <li>• Mains Input Voltage Range Selection: 150-260V</li> <li>• Input voltage: 120-260 volts</li> <li>• Output voltage: 220 volts</li> </ul> <p><b>2 years warranty</b></p>	13,700.00
40)	<p><b>P/F of 3000 VA, 36 volts Multi sine wave Inverter</b> with following specifications:</p> <ul style="list-style-type: none"> <li>• MICRO-CONTROLLER/DSC BASED Intelligent Control Design</li> <li>• Pure Sine Wave Output</li> <li>• PWM Controlled multistage ATM (Automatic Trickle Mode) Charging</li> <li>• Display Indications (Status &amp; Fault)</li> <li>• Smart Overload Sense and Short Circuit Protection</li> <li>• Easily Serviceable</li> <li>• Auto Reset Feature</li> <li>• Input voltage: 120-260 volts</li> <li>• Output voltage: 220 volts</li> </ul> <p><b>2 years warranty</b></p>	16,650.00
41)	<p><b>P/F of 4000VA , 48 volts Multi sine wave Inverter</b> with following specifications:</p> <ul style="list-style-type: none"> <li>• MICRO-CONTROLLER/DSC BASED Intelligent Control Design</li> <li>• Pure Sine Wave Output</li> <li>• PWM Controlled multistage ATM (Automatic Trickle Mode) Charging</li> <li>• Display Indications (Status &amp; Fault)</li> <li>• Smart Overload Sense and Short Circuit Protection</li> <li>• Easily Serviceable</li> <li>• Auto Reset Feature</li> <li>• Input voltage: 120-260 volts</li> <li>• Output voltage: 220 volts</li> </ul> <p><b>2 years warranty</b></p>	22,500.00
42)	<p><b>P/F of 6000VA , 72 volts Multi sine wave Inverter</b> with following specifications:</p> <ul style="list-style-type: none"> <li>• MICRO-CONTROLLER/DSC BASED Intelligent Control Design</li> <li>• Pure Sine Wave Output</li> <li>• PWM Controlled multistage ATM (Automatic Trickle Mode) Charging</li> <li>• Display Indications (Status &amp; Fault)</li> <li>• Smart Overload Sense and Short Circuit Protection</li> <li>• Easily Serviceable</li> <li>• Auto Reset Feature</li> <li>• Input voltage: 120-260 volts</li> <li>• Output voltage: 220 volts</li> </ul> <p><b>2 years warranty</b></p>	25,000.00
43)	Supply, Installation, commissioning and Testing of <b>Single In Single Out 10KVA UPS</b> stand alone/rack mountable working on, IGBT based double conversion digitally controlled microprocessor system, with with SNMP card & LCD display with Two year warranty	

	<p>Make (APC, )</p> <p><b>Specifications:</b></p> <ol style="list-style-type: none"> <li>1. <b>Technology: IGBT-PWM</b></li> <li>2. <b>AC Input Voltage : 192V AC ± 5V AC,</b></li> <li>3. <b>Output Voltage : 220V AC Phase to Nuetral ± 5% Voltage Regulation ± 1%</b></li> <li>4. <b>Frequency 50Hz ±0.05Hz( Crystal Controlled )</b></li> <li>5. <b>Waveform Pure Sine wave</b></li> <li>6. <b>Efficiency &gt; 92 %</b></li> <li>7. <b>20% overload limit for min 10 minutes.</b></li> </ol> <p><b>Battery Bank: (Sealed Maintenance Free Batteries, 3 year warranty)</b></p> <p><b>Nominal voltage: 12 Volts.</b>  <b>Rated capacity: 65 Ampere Hour (Ah).</b></p> <p><b>Dimensions</b>  Height (with terminals): 175 mm  Length: 351 mm  Width: 167 mm</p> <p><b>No. of batteries: 16 Nos (Make: Amaron/Exide/or equivalent)</b></p> <p>Battery bank for <b>1 hrs Min Back-up</b> along with <b>interconnecting cables, cable from UPS to Battery Bank through battery Circuit Breaker and MS open rack with Two years Maintenance.</b></p> <p><b>Protections:</b></p> <p>An Electronics Circuit with Digital Logics must Continuously Searches for the following Faults &amp; Trips the system with Audio - visual Indication</p> <ol style="list-style-type: none"> <li>1. <b>Battery over Voltage</b></li> <li>2. <b>Battery Under Voltage</b></li> <li>3. <b>Input AC Over Voltage</b></li> <li>4. <b>Output Overload /short Circuit</b></li> </ol> <p><b>Indications:</b></p> <ul style="list-style-type: none"> <li>• Main On</li> <li>• Load On Battery</li> <li>• Battery Low</li> <li>• Inverter Over load</li> <li>• Load On Main</li> <li>• Battery Boost</li> <li>• Battery Level Graph</li> <li>• Load Level Graph</li> </ul> <p><b>Features:</b>  Advanced Battery Management (ABM) for Longer Battery Life &amp; Quick Charging, Auto Self Test on LCD Display, Best Suited for most High Capacity Sophisticated Appliances, LCD Panel Display for Status and Faults, Static By Pass Switch for fast Switch Over.</p>	<p><b>4,15,000.00</b></p>
<p>44)</p>	<p>Supply, Installation, commissioning and Testing of <b>Single In Single Out 6 KVA UPS</b> stand alone/rack mountable working on, IGBT based double conversion digitally controlled microprocessor system, with with SNMP card &amp; LCD display with Two year warranty Make(APC, )</p> <p><b>Specifications:</b></p> <ol style="list-style-type: none"> <li>8. <b>Technology: IGBT-PWM</b></li> <li>9. <b>AC Input Voltage : 192V AC ± 5V AC,</b></li> <li>10. <b>Output Voltage : 220V AC Phase to Nuetral ± 5% Voltage Regulation ± 1%</b></li> <li>11. <b>Frequency 50Hz ±0.05Hz( Crystal Controlled )</b></li> </ol>	

	<p><b>12. Waveform Pure Sine wave</b>  <b>13. Efficiency &gt; 92 %</b>  <b>14. 20% overload limit for min 10 minutes.</b></p> <p><b><u>Protections:</u></b>  An Electronics Circuit with Digital Logics must Continuously Searches for the following Faults &amp; Trips the system with Audio – visual Indication</p> <p><b>1. Battery over Voltage</b>  <b>2. Battery Under Voltage</b>  <b>3. Input AC Over Voltage</b>  <b>4. Output Overload /short Circuit</b></p>	<b>65,500.00</b>
45)	<p>Supply, Installation, commissioning and Testing of <b>Single In Single Out 2KVA</b> stand alone/rack mountable working on, IGBT based double conversion digitally controlled microprocessor system, with SNMP card &amp; LCD display with Two year warranty Make(APC, )</p> <p><b><u>Specifications:</u></b></p> <p><b>15. Technology: IGBT-PWM</b>  <b>16. AC Input Voltage : 72/96V AC ± 5V AC,</b>  <b>17. Output Voltage : 220V AC Phase to Nuetral ± 5% Voltage Regulation ± 1%</b>  <b>18. Frequency 50Hz ±0.05Hz( Crystal Controlled )</b>  <b>19. Waveform Pure Sine wave</b>  <b>20. Efficiency &gt; 92 %</b>  <b>21. 20% overload limit for min 10 minutes.</b></p> <p><b><u>Protections:</u></b>  An Electronics Circuit with Digital Logics must Continuously Searches for the following Faults &amp; Trips the system with Audio – visual Indication</p> <p><b>1. Battery over Voltage</b>  <b>2. Battery Under Voltage</b>  <b>3. Input AC Over Voltage</b>  <b>4. Output Overload /short Circuit</b></p>	<b>25,700.00</b>
46)	<p>P/F of VRLA-Dry sealed Maintenance free batteries of 12 volts of capacity <b>42 Ampere hour Ah.</b>  Make: Amaron,Exide or equivalent</p>	<b>7,950.00</b>
47)	<p>P/F of VRLA- Dry sealed Maintenance free batteries of 12 volts of capacity <b>65 Ampere hour Ah.</b>  Make: Amaron,Exide or equivalent</p>	<b>9,700.00</b>
48)	<p>P/F of VRLA- Dry sealed Maintenance free batteries of 2 volts of capacity <b>60 Ampere hour Ah.</b></p>	<b>4,350.00</b>
49)	<p>P/F of 1200 mm sweep Metallic ceiling fan with 300 watt 5 step regulator of and hook for fan. The job includes providing of fan hook in wooden/concrete ceiling wherever needed. Complete in all respects.</p>	<b>2200.00</b>
50)	<p>P/F of 1400mm sweep Metallic ceiling fan with 300 watt 5 step regulator of and hook for fan. The job includes providing of fan hook in wooden/concrete ceiling wherever needed. Complete in all respects.</p>	<b>2,500.00</b>
51)	<p>P/F of 1200mm sweep Decorative Oyster-Matallic/Fussion-II Metallic ceiling fan with 300 watt 5 step regulator and hook for fan. The job includes providing of fan hook in wooden/concrete ceiling wherever needed. Complete in all respects.</p>	<b>3,700.00</b>
52)	<p>P/F of 1200mm sweep <b>Decorative TYRO / QITE / ASPIRE / ROVER</b> (make standard) Premium Metallic ceiling fan with 300 watt 5 step regulator and hook for fan. The job includes providing of fan hook in wooden/concrete ceiling wherever needed. Complete in all respects.</p>	<b>4,200.00</b>
53)	<p>P/F of 1400mm sweep Decorative Oyster-Matallic/Fussion-II Metallic ceiling fan with 300 watt 5 step regulator and hook for fan. The job includes providing of fan hook in wooden/concrete ceiling wherever needed. Complete in all respects.</p>	<b>3700.00</b>

54)	P/F of 300 mm Sweep Heavy Duty Crompton Greaves Exhaust Fan (metal type) in existing opening, including making good the damage, connection, testing, commissioning etc. as required. Complete in all respects.	<b>3200.00</b>
55)	P/F of 450 mm Sweep, single phase 4 pole Heavy Duty Crompton Greaves Exhaust fan (metal type) in existing opening, including making good the damage, connection, testing, commissioning etc. as required. Complete in all respects.	<b>4500.00</b>
56)	P/F of 400 mm sweep, speed 2400 RPM Swing GYRO Cabin Fan with 300 Watt 5 step regulator of Modular Series. Complete in all respects.	<b>3000.00</b>
57)	P/F of 400 mm sweep , Speed 2100 RPM SDX Black Gold Wall Fan with 300 Watt 5 step regulator of Modular Series. Complete in all respects.	<b>2500.00</b>
58)	P/F of 400 mm sweep Swing Wall Fan of Havells or equivalent Khaitan make with 300 Watt 5 step regulator of Pointer/ havells/Anchor make. Complete in all respects.	<b>2700/-</b>
<b>Underground Power Cables</b>		
59)	Supplying and laying of one XLPE insulated & PVC sheathed aluminum conductor armoured power cable of 1.1kv grade of following size in the existing RCC/HUME/STONEWARE/METAL or direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Complete in all respects.	
60)	3.5c × 25 sq mm	<b>350.00</b>
61)	3.5c × 35 sq mm	<b>396.00</b>
62)	3.5c × 50 sq mm	<b>516.00</b>
63)	3.5c × 70 sq mm	<b>690.00</b>
64)	3.5c × 95 sq mm	<b>865.00</b>
65)	3.5c × 120 sq. mm	<b>1180.00</b>
66)	3.5c × 150 sq. mm	<b>1380.00</b>
67)	3.5c × 185 sq. mm	<b>1740.00</b>
68)	3.5c × 240 sq. mm	<b>2220.00</b>
69)	3.5c × 300 sq. mm	<b>2673.00</b>
70)	3.5c × 400 sq. mm	<b>3099.00</b>
71)	Supply and Laying of PVC Insulated and FR PVC round sheathed, armoured solid copper conductor industrial cable of 1.1kv grade of following sizes in suitable size conduits. Complete in all respects.	
72)	3 core 1.5 sq mm cable	<b>153.00</b>
73)	3 core 2.5 sq mm cable	<b>186.00</b>
74)	3 core 4 sq mm cable	<b>210.00</b>
75)	3 core 6 sq mm cable	<b>330.00</b>
76)	3 core 10 sq mm cable	<b>547.00</b>
77)	3 core 16 sq mm cable	<b>866.00</b>
78)	4 core 4 sq mm cable	<b>280.00</b>
79)	4 core 6 sq mm cable	<b>420.00</b>
80)	4 core 10 sq mm cable	<b>726.00</b>
81)	4 core 16 sq mm cable	<b>1128.00</b>
82)	Supplying and Laying DWC HDPE pipe as per IS14930 (Part-II) complete with fitting and accessories in ground at the depth of 75cm laying of cable including excavation and refilling the trench etc as required.	
83)	(OD)/ (ID) 50mm / 39mm	<b>175.00</b>
84)	(OD)/ (ID) 90mm /76mm	<b>245.00</b>
85)	(OD)/(ID)120mm/103mm	<b>305.00</b>
86)	Supply and Installation of PVC raceway including cover and accessories (Bends, Joints, End Caps complete in all respects) of the following sizes: Make: Legrand/ Hager or equivalent	
	150 mm width × 100 mm depth.	<b>1,530.00</b>
	300 mm width × 100 mm depth.	<b>1,850.00</b>

87)	Supplying and making straight through cable jointing with high quality cast resin compound, including ferrule and other jointing materials, for following size of 3.5 core, XLPE aluminum conductor cable of 11 KV grade as required. The job includes excavation and refilling of trench. complete in all respects.	
	70 sq mm	<b>12,350</b>
b)	120 sq mm	<b>15,300</b>
	240 sq mm	<b>18,300</b>
	300 sq mm	<b>21,550</b>
	400 Sq mm	<b>23,600</b>
<b>Street Lights / Luminaries / Tube-lights / Garden Lights</b>		
88)	<b>SOLAR LIGHT</b> Supply of LED Post Top with a system lumen output of 2000 lumens and a minimum system efficacy of 80lm/W. The luminaire shall have a rated system lifetime of 25,000 burning hours at L70. The luminarie should have a color temperature of 4000K and CRI > 70. The luminaries shall meet IP65 with THD < 20% and PF > 0.9. The luminaries shall have closed diffused optics with polycarbonate diffuser board. The total power consumption should not exceed 30W (including driver). Similar to Philips Make LED POST TOP G3 "BGP161 LED2500/NW PSU 220-240V 7043 IN	<b>21,000.00</b>
89)	<b>Sports Lights (BVP410,Phillips):</b> Supply of LED based Flood light, housing made up of pressure die cast aluminum Alloy with effective thermal management, sturdiness and embossed brand name/logo name of manufacturer. The fixture should have a minimum system efficacy of 100 lumen/Watt and a minimum system lumen output of 16500 lumens and maximum system wattage of 165 Watts. The fixture shall have a CRI of minimum 70. The fixture should have asymmetric/ symmetric narrow beam and Narrow beam angle options available. The fixture shall be designed for a system life of 50,000 hours @70% lumen maintenance. Ingress Protection of IP66 (lamp and gear Compartment) and Mechanical Impact Resistance Rating of IK >=05.The fixture driver should have an operating voltage range of 140-270 V, surge protection of >=3KV, PF >0.9 and THD<20%. The fixture should comply with the parameters as per IS10322. The LED driver should comply to IEC61000-3-2 ed.3.2, 2009 for Harmonics, IEC61347 -2 -13, 2006 in Conjunction with IEC61347-1 ed.2.0, 2007 for Electrical Safety, IEC62384 ed.1.1, 2011 for performance and IEC61547 ed.2.0, 2009, CISPR-15 for EMI. Manufacturer shall have in-house lab approved by NABL or ministry of science of govt of India. LM 79 and LM80 reports need to be submitted from a NABL/UL accredited lab to verify above parameters. Similar to Philips BVP410.. complete in all respects	<b>25,500.00</b>
90)	<b>Street Light (Type BRP410, Phillips):</b> Supply & Installation of LED based Flood light, housing made up of Pressure Die Cast Housing LM 6 Alloy/ Anti Dust Exposed Lens, sturdiness and embossed brand name/logo name of manufacturer. The fixture should have a minimum system efficacy of 100 lumen/Watt and a minimum system lumen output of 7200 lumens and maximum system wattage of 72 Watts. The fixture shall have a CRI of minimum 70. The fixture shall be designed for a system life of 50,000 hours @70% lumen maintenance. Ingress Protection of IP66 (lamp and gear Compartment) and Mechanical Impact Resistance Rating of IK >=05.The fixture driver should have an operating voltage range of 140-270 V, surge protection of >=3KV, PF >0.9 , THD<20% and SDCM<5. The driver should be BIS approved, fully potted and encapsulated .The fixture should comply with the parameters as per IS10322. The LED driver should comply to IEC61000-3-2 ed.3.2, 2009 for Harmonics, IEC61347 -2 -13, 2006 in Conjunction with IEC61347-1 ed.2.0, 2007	

	for Electrical Safety, IEC62384 ed.1.1, 2011 for performance and IEC61547 ed.2.0, 2009, CISPR-15 for EMI. Manufacturer shall have in-house lab approved by NABL or ministry of science of govt of India. LM 79 and LM80 reports need to be submitted from a NABL/UL accredited lab to verify above parameters. Similar to Philips CAT No. - BRP410 LED CW 072 MR FG S1 PSU GR. Complete in all respects	<b>18,900.00</b>
a)	<b><u>Street Light (Type BRP410, Phillips):</u></b> Supply of LED based Flood light, housing made up of Pressure Die Cast Housing LM 6 Alloy/ Anti Dust Exposed Lens, sturdiness and embossed brand name/logo name of manufacturer. The fixture should have a minimum system efficacy of 100 lumen/Watt and a minimum system lumen output of 7200 lumens and maximum system wattage of 72 Watts. The fixture shall have a CRI of minimum 70. The fixture shall be designed for a system life of 50,000 hours @70% lumen maintenance. Ingress Protection of IP66 (lamp and gear Compartment) and Mechanical Impact Resistance Rating of IK >=05.The fixture driver should have an operating voltage range of 140-270 V, surge protection of >=3KV, PF >0.9 , THD<20% and SDCM<5. The driver should be BIS approved, fully potted and encapsulated .The fixture should comply with the parameters as per IS10322. The LED driver should comply to IEC61000-3-2 ed.3.2, 2009 for Harmonics, IEC61347 -2 -13, 2006 in Conjunction with IEC61347-1 ed.2.0, 2007 for Electrical Safety, IEC62384 ed.1.1, 2011 for performance and IEC61547 ed.2.0, 2009, CISPR-15 for EMI. Manufacturer shall have in-house lab approved by NABL or ministry of science of govt of India. LM 79 and LM80 reports need to be submitted from a NABL/UL accredited lab to verify above parameters. Similar to Philips CAT No. - BRP410 LED CW 072 MR FG S1 PSU GR. Complete in all respects	<b>16,500.00</b>
91)	P/F of <b>25 Watt LED ROCKET BULBs</b> B22/E27/E40 base, 6500k, Input Volt (AC 90-300V) <b>&gt;100 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	<b>1050.00</b>
92)	P/F of <b>35 Watt LED ROCKET BULBs</b> B22/E27/E40 base, 6500k, Input Volt (AC 90-300V) <b>&gt;100 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	<b>1,250.00</b>
93)	P/F of <b>45 Watt LED ROCKET BULBs</b> B22/E27/E40 base, 6500k, Input Volt (AC 90-300V) <b>&gt;100 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	<b>1,500.00</b>
94)	Supply , installation ,Testing and commissioning of 100W , 10000 lm Smart Bright LED Flood Light (White Light) Input Volt (AC 90-300V) <b>&gt;120 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	9,500.00
95)	Supply , installation ,Testing and commissioning of 70W Smart Bright LED Flood Light (White Light) Input Volt (AC 90-300V) <b>&gt;120 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	7,200.00
96)	Supply , installation ,Testing and commissioning of 50W Smart Bright LED Flood Light (White Light) Input Volt (AC 90-300V) <b>&gt;120 lumens per watt</b> with Aluminum and thermoplastic glass housing and having long life span of upto 50,000 hrs. complete in all respects.	4,700.00
97)	P/F of high lumen LED 6500k (2 ft) wall mounted LED batten, extruded aluminum heat sink provided for efficient heat dissipation & integrated electronic driver complete in all respects. Complete in all respects. (Make Phillips TYPE: BN 021 LED25S 6500 PSU GR S1).	1,000.00
98)	P/F of high lumen LED 6500k (4ft ft) wall mounted LED batten, extruded aluminum heat sink provided for efficient heat dissipation & integrated electronic driver complete in all respects. Complete in all respects.	2,250.00
99)	P/F of HIGHER WATTAGE decorative ultra slim square profile LED fixture with high lumen output of 24 W LED 6000k (4 ft) wall mounted LED batten, extruded aluminum heat sink provided for efficient heat dissipation & integrated electronic driver complete in all respects.	450.00
100)	P/F of 2 ft*2ft LED luminaries with URG <19 recess mounted with high lumen output with durable housing with Al heat sink with Diffuser to give glare free light with removable driver.	5,300.00

	(Make Phillips TYPE RC380B LED30S-6500G4 L60 W60 PSU OD OC)	
101)	P/F of 2 ft*2ft LED luminaries with URG <19 recess mounted with high lumen output with durable housing with Al heat sink with Diffuser to give glare free light with removable driver. (Make Phillips TYPE RC380B LED 36 S -6500G4 L60 W60 PSD OD WH OC)	7,300.00
102)	P/F of Suspended / Surface mounted LED Luminaries with diffused optics, extruded aluminum heat sink provided for heat dissipation and integrated electronic Driver complete in all respects. System efficacy more than 100 Lm/W <ul style="list-style-type: none"> <li>• Superior light quality with CRI more than 80</li> <li>• THD Less than 10%</li> <li>• Wide operating voltage 140-270V</li> <li>• Suitable for Standalone &amp; Continuous Mounting</li> <li>• Option of Dimming available</li> <li>• Up-Down lighting distribution</li> <li>• Uniform &amp; volumetric light distribution</li> </ul> Make: (Philips SP680P LED34S 6500 PSU WH L120 S1)	7,300.00
103)	P/F of Suspended / Surface mounted LED Luminaries with diffused optics, extruded aluminum heat sink provided for heat dissipation and integrated electronic Driver complete in all respects. System efficacy more than 100 Lm/W <ul style="list-style-type: none"> <li>• Superior light quality with CRI more than 80</li> <li>• THD Less than 10%</li> <li>• Wide operating voltage 140-270V</li> <li>• Suitable for Standalone &amp; Continuous Mounting</li> <li>• Option of Dimming available</li> <li>• Up-Down lighting distribution</li> <li>• Uniform &amp; volumetric light distribution</li> </ul> ( Make Philips Type : SM270C LED 30S 6500 PSU WH)	6,000.00
104)	P/F of Suspended / Surface mounted LED Luminaries with 135mm diffused compartment, for Armstrong techzone ceiling, extruded aluminum heat sink provided for heat dissipation and integrated electronic Driver complete in all respects. System efficacy more than 100 Lm/W <ul style="list-style-type: none"> <li>• Superior light quality with CRI more than 80</li> <li>• THD Less than 10%</li> <li>• Wide operating voltage 140-270V</li> <li>• Suitable for Standalone &amp; Continuous Mounting</li> <li>• Option of Dimming available</li> <li>• Up-Down lighting distribution</li> <li>• Uniform &amp; volumetric light distribution</li> </ul> (Make Philips: RC820B LED 26S 6500 PSU W15 L120 OD SI)	8,500.00
105)	Supply and Fixing of Aluminum enclosure LED Based hanging light for office tables , 20W inbuilt LED light, 120lm per watt , 4500k, Ip-Op (220-240V). Complete in all respects.	1,760.00
106)	P/F of Bolt Round LED 6500k, 2000 Lumens Surface/ recess mounted round shaped LED down-lighter with durable housing with Al heat sink with Diffuser to give glare free light with removable driver. Complete in all respects. (Make Phillips TYPE: SM251C LED16S 6500 PSU WH)	1,800.00
107)	P/F of Bolt Round 10W LED 6000k Surface/ recess mounted round shaped LED down-lighter with durable housing with Al heat sink with Diffuser to give glare free light with removable driver. Complete in all respects. (Make Phillips TYPE : DN092B LED10S 6500 PSU WH)	2,200.00
108)	P/F of Bolt Round 15W LED 6500k Surface/ recess mounted round shaped LED down-lighter with durable housing with Al heat sink with Diffuser to give glare free light with removable driver. Complete in all respects.	1,300.00

109)	P/F of Endura LED bulkhead with IP 66 protection and IK08 impact resistance suitable for surface and wall mount luminaries with Opal Diffuser Energy saving. Complete in all respects. <b>(Make Type WT140W LED7S CWPSUS1 PC)</b>	<b>1,050.00</b>
110)	P/F of Endura LED bulkhead with IP 66 protection and IK08 impact resistance suitable for surface and wall mount luminaries with Opal Diffuser Energy saving. Complete in all respects. <b>(Make Type WT202W LED6SNW PSUS2PC)</b>	<b>1,670.00</b>
111)	P/F of Endura City liner Neo 48W LED 6000k, energy saving & environmental friendly long life Versatile pressure die-cast aluminum IP65 roadway/street light luminaire with high power LED as light source and Electronic Driver.(Suitable for pole dia 35mm max). Complete in all respects.	<b>8,000.00</b>
112)	P/F of 45 watt CFL spiral type.	<b>350.00</b>
113)	Supply Installation of 2.5 meter ornamental pole <b>(Antique IV)</b> of mild steel (grooved) with cast iron base of Hi-Lite / Homedec /Jaguar make and embellishment having corrosion and UV resistant coating, including cost of concrete foundation and foundation bolts. Complete in all respects.	<b>12,500.00</b>
114)	Supply, Installation and commissioning of ornamental 2 arm bracket for installation of multiple lights <b>and</b> cast Aluminum lighting fixture with mild steel bracket having integral 25W LED lighting source with acrylic diffuser. The fixture shall have corrosion and UV ray resistant coating shall be compatible with the specified pole shall have stainless steel crews and shall be ingress protection of IP. Complete in all respects.	<b>6,500.00</b>
115)	Supply Installation of 3 meter ornamental/Decorative pole <b>(Antique III)</b> of mild steel (grooved) with cast iron base of Hi-Lite / Homedec /Jaguar make and embellishment having corrosion and UV resistant coating, including cost of concrete foundation and foundation bolts. Complete in all respects.	<b>8,500.00</b>
116)	Supply, Installation and commissioning of ornamental/Decorative 2 arm bracket for installation of multiple lights <b>and</b> cast Aluminum lighting fixture with mild steel bracket having integral 25W LED lighting source with acrylic diffuser. The fixture shall have corrosion and UV ray resistant coating shall be compatible with the specified pole shall have stainless steel crews and shall be ingress protection of IP. Complete in all respects.	<b>4,500.00</b>
117)	Supply , Installation and commissioning of 3.5 meter Aesthetically designed havells make (ordering code LHMP02135099) decorative hot dipped galvanized mild steel steep pole with grey powder finish. The job includes fixing of 25W 600k LED with suitable circuit. Complete in all respects.	<b>15,000.00</b>
118)	Supply, Installation and commissioning of long life aesthetically designed aluminum landscape luminaries <b>(Bamboo-IP 65,)</b> for diffused lighting with high power LED (15W , 5700k) as light source. Complete in all respects.	<b>6,500.00</b>
119)	Supply, Installation and commissioning of long life aesthetically designed aluminum landscape luminaries <b>(CONE-IP 65, )</b> for diffused lighting with high power LED (15W , 5700k) as light source. Complete in all respects.	<b>6,500.00</b>
120)	Supply of LED Ground Mounted Bollard 0.5m height with a system lumen output of 300 lumens and a minimum system efficacy of 35 lm/W. The luminaire shall have a rated system lifetime of 25,000 burning hours at L70. The luminaire should have a color temperature of 4000K and CRI>75. The luminaire shall meet IP65 & IK10 rating with THD < 20% and PF > 0.9. The luminaire housing should made of pressure die cast aluminium with polycarbonate diffuser. The total power consumption should not exceed 7W (including driver). <b>Philips Make LED BOLLARD II "BCP150 LED150/NW PSU 220-240V 7043"</b>	12,000.00
121)	Supply of CITY CUBE BOLLARD DLED Ground Mounted Bollard 0.5m height with a system lumen output of 300 lumens and a minimum system efficacy of 35 lm/W. The luminaire shall have a rated system lifetime of 25,000 burning hours at L70. The luminaire should have a color temperature of 4000K and CRI>75. The luminaire shall meet IP65 & IK10 rating with THD < 20% and PF > 0.9. The luminaire housing should made of pressure die cast aluminium with polycarbonate diffuser. The total power consumption should not exceed 7W (including driver). <b>(PHILIPS MAKE CITYCUBE BOLLARD D BCP400 LED09 D CW PSU GR S1)</b>	12,500.00



122)	Supply, Installation and commissioning of 40W LED 6000k ( <b>Industrial luminaries</b> ) long life Endura Well Glass NEO-IP65, vertical/horizontal surface mounting or suspended type pressure die cast aluminum with high power LED light source. Complete in all respects.	<b>4,500.00</b>
MCCBs/MCBs/LT Distribution Panels		
123)	P/F of 4- pole, 800 Amp. MCCB (Adjustable type) compact NS, Icu = 50kA as per IEC 60947-2 (cat no. INA_3P33466E) fixed type having electronic trip unit with adjustable overload protection 0.4-1 xIn of Schneider / Legrand/L&T including spreaders of same rating. Complete in all respects.	<b>65,500.00</b>
124)	P/F of 4- pole, 630 Amp. MCCB (Adjustable type) Easycompact CVS, Icu = 50kA (cat no. LV563316) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider/Legrand/L&T make including spreaders of same rating. Complete in all respects.	<b>51,500.00</b>
125)	P/F of 4- pole, 400 Amp. MCCB (Adjustable type) Easycompact CVS, Icu = 50kA (cat no. LV540316) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider /Legrand/L&T make including spreaders of same rating. Complete in all respects.	<b>41,500.00</b>
126)	P/F of 4- pole, 250 Amp. MCCB (Adjustable type) Easy compact CVS, Icu = 36kA (cat no. LV525333) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider /Legrand/L&T make including spreaders of same rating. Complete in all respects.	<b>26,750.00</b>
127)	P/F of 4- pole, 160 Amp. MCCB (Adjustable type) Easy compact CVS, Icu = 25kA (cat no. LV516303) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider /Legrand/L&T make including spreaders of same rating. Complete in all respects.	<b>16,850.00</b>
128)	P/F of 4- pole, 125 Amp. MCCB (Adjustable type) Easy compact CVS, Icu = 25kA (cat no. LV516303) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider /Legrand/L&T make including spreaders of same rating. Complete in all respects.	12,800.00
129)	P/F of 4- pole, 100 Amp. MCCB (Adjustable type) Easy compact CVS, Icu = 25kA (cat no. LV516303) fixed type with Ics = 100% Icu as per IEC 60947-2 of Schneider /Legrand/L&T make including spreaders of same rating. Complete in all respects.	11,900.00
130)	63 Amps. 4P MCCB of breaking capacity 25 KA (Cat No: LV510305) with thermal magnetic release ICU=Ics=100%, necessary spreader terminals and phase barriers on incoming & outgoing side complete as required (for outgoing).	11,500.00
131)	Supplying, installing on wall testing & commissioning of following made of <b>1.6 mm thick double door sheet steel enclosure</b> duly painted with powder coating, wall straps, fully PVC insulated <b>4 Nos Aluminum bus bars of 10 mm×40mm×400mm Dimension</b> in convenient sections & suitable for 415 volts(with voltmeter), 3 phase (with indicators), 4 wire, 50HZ, A.C. Supply with extension joints, fire proof barriers, expansion joints, thrust pads including jointly & earthing with 2 runs of galvanised iron strips etc as required. <b>The Size of the Busbar Enclosure must be 1.5ft×1.5ft×0.8ft (l,w,d) in dimension. complete in all respects.</b>	
132)	<b>200A 4-Strip Aluminum Busbar</b>	<b>13,500.00</b>
133)	Supplying, installing on wall testing & commissioning of following capacity rising mains made of <b>1.6 mm thick double door sheet steel enclosure</b> duly painted with powder coating, wall straps, fully PVC insulated <b>4 Nos Aluminum bus bars of 10mm×30mm×100mm</b> in convenient sections & suitable for 415 volts(with voltmeter), 3 phase (with indicators), 4 wire, 50HZ, A.C. Supply with extension joints, fire proof barriers, expansion joints, thrust pads including jointly & earthing with 2 runs of galvanized iron strips etc as required. <b>The Size of the Busbar Enclosure must be 1.2ft×1.2ft×0.5ft (l,w,d) in dimension. complete in all respects.</b>	
134)	<b>100A 4-Strip Aluminum Busbar</b>	<b>9,500.00</b>
135)	Supplying, installing on wall testing & commissioning of following made of <b>1.6 mm thick double door sheet steel enclosure</b> duly painted with powder coating, wall straps, fully PVC insulated <b>4 Nos Aluminum bus bars of 12 mm×50mm×450mm Dimension</b> in convenient sections & suitable for 415 volts(with voltmeter), 3 phase	

	(with indicators), 4 wire, 50HZ, A.C. Supply with extension joints, fire proof barriers, expansion joints, thrust pads including jointly & earthing with 2 runs of galvanised iron strips etc as required. <b>The Size of the Busbar Enclosure must be 2ft×2ft×1ft (l,w,d) in dimension. complete in all respects.</b>	
136)	400 A 4-Strip Aluminum Busbar	<b>18,500.00</b>
137)	Supplying and Laying of one No. HT. cable of 11 KV grade XLPE armoured Al. Conductor earthed conforming to IS 7098 (Part II) and of size <b>3 X 240</b> sq mm in the suitable pipe /masonry open duct enclosed with iron plate etc as required.	<b>3,100.00</b>
138)	Supplying and making indoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs and other jointing material for 3 x 240 Sq mm. XLPE aluminum conductor cable of 11 KV grade as required.	<b>15,500.00</b>
139)	Supplying and fixing 63 A rating, 240/415 V, 16kA "C"curve, Double Pole miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	<b>1750.00</b>
140)	Supplying and fixing <b>63A rating, 415 V, 16kA "C"curve, Four Pole Miniature Circuit Breaker</b> suitable for Heavy inductive load ,in the MCB DB complete with connections, testing and commissioning etc. as required.	<b>3,950.00</b>
141)	Supplying and fixing <b>100A rating, 415 V, 16kA "C"curve, Four Pole Miniature Circuit Breaker</b> suitable for Heavy inductive load ,in the MCB DB complete with connections, testing and commissioning etc. as required.	<b>14,200.00</b>
142)	Digital Voltmeter with selector switch and LED indication lights on each phase protected by HRC back up fuses MCBs.	<b>3,000.00</b>
143)	Digital Ampere meter Along with selector switch and suitable rating/ratio of current transformers.	<b>2,000.00</b>
144)	Supplying, installation, testing & commissioning of <b>OUTDOOR Panel</b> factory assembled Dust & Vermin Proof LT cubical type compartmentalized panel of <b>600 A TPN Aluminum Busbar (12mm thickness) panel</b> (CPRI Approved) fabricated out of 2 mm thick MS sheet, <b>300 mm Deep</b> with locking arrangement, cable alleys, bus bar chamber etc powder coated self supported suitable for 3 phase 4 wire, AC supply, i/c supplying & fixing following accessories as detailed below, i/c bus bars connections / inter connections to MCCB compartments , arrangement for cable entry, supports, end terminations, 2 Nos. earthing stud inter connection with 25mm x 5mm GI strip (externally), painting, etc. complete as required. <b>(panel should be 2.5 feet above ground including Iron Stand as per requirement &amp; as and when required)</b>	<b>30,500/sq mtr</b>
145)	Supplying, installation, testing & commissioning of <b>OUTDOOR Panel</b> factory assembled Dust & Vermin Proof LT cubical type compartmentalized panel of <b>400A TPN Aluminum Busbar (10mm thickness) panel</b> (CPRI Approved) fabricated out of 2 mm thick MS sheet, <b>300mm Deep</b> with locking arrangement, cable alleys, bus bar chamber etc powder coated self supported suitable for 3 phase 4 wire, AC supply, i/c supplying & fixing following accessories as detailed below, i/c bus bars connections / inter connections to MCCB compartments , arrangement for cable entry, supports, end terminations, 2 Nos. earthing stud inter connection with 25mm x 5mm GI strip (externally), painting, etc. complete as required. <b>(panel should be 2.5 feet above ground including Iron Stand as per requirement &amp; as and when required)</b>	<b>26,700/sq mtr</b>
146)	Supplying, installation, testing & commissioning of <b>INDOOR Panel</b> factory assembled Dust & Vermin Proof wall / floor mounted LT cubical type compartmentalized panel of <b>300 A TPN Aluminum Busbar (10mm thickness) panel</b> (CPRI Approved) fabricated out of 2 mm thick MS sheet, <b>300mm Deep</b> with locking arrangement, cable alleys, bus bar chamber etc powder coated self supported suitable for 3 phase 4 wire, AC supply, i/c supplying & fixing following accessories as detailed below, i/c bus bars connections / inter connections to MCCB compartments , arrangement for cable entry, supports, end terminations, 2 Nos. earthing stud inter connection with 25mm x 5mm GI strip (externally), painting, etc. complete as required. <b>The compartmentalized panel consisting of various outgoing compartments for 63/125/160/ A MCCBs with a minimum space of 200 mm between each outgoing compartments. (panel should be 2.5 feet above ground including</b>	<b>22,700/sq mtr</b>

	<b>Iron Stand as per requirement &amp; as and when required)</b>	
147)	Supplying, installation, testing & commissioning of <b>INDOOR Panel</b> factory assembled Dust & Vermin Proof wall / floor mounted LT cubical type compartmentalized panel of <b>200 A TPN Aluminum Busbar (10mm thickness) panel</b> (CPRI Approved) fabricated out of 2 mm thick MS sheet, <b>300mm Deep</b> with locking arrangement, cable alleys, bus bar chamber etc powder coated self supported suitable for 3 phase 4 wire, AC supply, i/c supplying & fixing following accessories as detailed below, i/c bus bars connections / inter connections to MCCB compartments , arrangement for cable entry, supports, end terminations, 2 Nos. earthing stud inter connection with 25mm x 5mm GI strip (externally), painting, etc. complete as required. <b>The compartmentalized panel consisting of various outgoing compartments for 63/125/160/ A MCCBs with a minimum space of 200 mm between each outgoing compartments. (panel should be 2.5 feet above ground including Iron Stand as per requirement &amp; as and when required)</b>	18,850/sq mtr
148)	Supply and Installation of <b>Extended rotatory handle panel mounted</b> for MCCBs with clear indication of ON/OFF /Trip Indication and having IP 54 degree of protection. <b>(For 100/160/250A MCCBs)</b>	1,900.00
149)	Supply and Installation of <b>Extended rotatory handle panel mounted</b> for MCCBs with clear indication of ON/OFF /Trip Indication and having IP 54 degree of protection. <b>(For 400/630 A MCCBs)</b>	2,850.00
150)	Supply and Installation of <b>3 phase 415 Volt Digital voltmeter and 3-phase Ammeter with separate indicators for each phase</b> mounted on top of the front side of panel including all connections.	3,500.00
151)	SITC of 8 way (100A MCCB + 24) (Ref: A9HVD08L) Double Door Metal (IP-43) VTPN DBs for MCCB Incomer DBs for higher incoming current distribution up to 100A Incomer - TP/FP ComPact NSX or EasyPact CVS MCCB up to 100A Outgoing - SP MCBs / TP MCBs	18,500.00
152)	SITC of 12 way (100A MCCB + 36) (Ref: A9HVD12L) Double Door Metal (IP-43) VTPN DBs for MCCB Incomer DBs for higher incoming current distribution up to 100A Incomer - TP/FP ComPact NSX or EasyPact CVS MCCB up to 100A Outgoing - SP MCBs / TP MCBs	23,750.00
153)	SITC of 12 way (160A MCCB + 36) (Ref: A9HVD12M) Double Door Metal (IP-43) VTPN DBs for MCCB Incomer DBs for higher incoming current distribution up to 160A Incomer - TP/FP ComPact NSX or EasyPact CVS MCCB up to 160A Outgoing - SP MCBs / TP MCBs	24,500.00
154)	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)	
	12 way (4 + 36), Double door	6,500.00
155)	Supply and Installation of Schneider Electric DM3110-30002385 Three Phase 4 LED display Ammeter with following specifications: Model No: DM3110-30002385 Current input: 50mA-6A Accuracy : 1 Voltage: 90-280V	2,000.00
156)	Supply, Installation, Testing And Commissioning of Air Circuit Breaker 4 pole, 50 Hz, current rating 2500 Amps , 50 KA with microprocessor release type, (Ics : 100% Icu) with Adjustable setting of ground fault, Overload, Short Circuit Protection fitted with spreader links & Phase separators.	2,40,000.00
157)	Supply, Installation ,Testing and Commissioning of HT 12KV, 630 Amps, 3Phase 50Hz, Breaking capacity 26.3 kA, Making Capacity 67 kAp totally metal clad withdraw able type Vacuum Circuit Breaker with Copper bus bar of suitable rating, horizontal isolation type VCB of capacity minimum 630 Amps rated current, as per IEC 62271-100-200.The offered panels shall be tested for IAC level of 21kA/3 sec (CG/Schneider/L&T only) for better performance.	2,70,000.00
158)	Supply, Installation, Testing and commissioning of 7/8 mtrs long octagonal pole	

	galvanized continuously tapered (bolt fixing type) in single section made out of 3mm thick sheet having top dia 70mm and bottom dia 130mm with 4 nos hot dip galvanized foundation bolts of size 20mm dia × 700 long with integral junction box/base plate (200×220×16mm) along with suitable size of GI single arm bracket 1500mm long i/c providing and fixing bakelite sheet of size 25cm×10cm×6cm thick, connector, 2nos al busbar of suitable size and SP MCB of 6 amp rating inside the pole atleast 1.25 mtrs above from bottom of pole complete with door and locking arrangements etc as required. Complete in all respects.	20,500.00
159)	Dismantling of the R.C.C./ pole of 7 meters with brick masonry support and the dismantled material / poles have to dumped or staged by the contractor at a site to be decided by the concerned Division. Complete in all respects.	<b>1850.00</b>
160)	Dismantling of the steel tabular pole/iron pole of 7 meters with brick masonry supports and the dismantled material / poles have to be dumped or staged by the contractor at a site to be decided by the concerned Division. Complete in all respects.	<b>1350.00</b>
<b>CCTV Cameras, Modules and Switches / Telephone wires</b>		
161)	Supply and Laying of 100 pair jelly filled Armoured telephone cable of 0.5 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. The cable is to be laid drawn by Horizontal Directional Drilling in permanently lubricated Duct (PLB Duct). Complete in all respects.	1110/mtr
162)	Supply and Laying of 50 pair jelly filled Armoured telephone cable of 0.5 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. The cable is to be laid drawn by Horizontal Directional Drilling in permanently lubricated Duct (PLB Duct). Complete in all respects.	<b>665/meter</b>
163)	Supply and Laying of 20 pair jelly filled Armoured telephone cable of 0.5 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. The cable is to be laid drawn by Horizontal Directional Drilling including permanently lubricated Duct (PLB Duct). Complete in all respects.	<b>282/meter</b>
164)	Supply and Laying of 10 pair jelly filled Armored telephone cable of 0.5 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. Complete in all respects.	<b>245/meter</b>
165)	Supply and Laying of 10 pair jelly filled unarmored telephone cable of 0.4 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, laid in PVC pipe as and when required.Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. Complete in all respects.	<b>135/meter</b>
166)	Supply and Laying of 5 pair jelly filled unArmoured telephone cable of 0.4 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, laid in PVC pipe as and when required.Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. Complete in all respects.	<b>95/Meter</b>
167)	Supply and Laying of 2 pair jelly filled unArmoured telephone cable of 0.4 mm copper conductor Dia with Soft-Annealed Solid Electrolytic Copper, laid in PVC pipe as and when required. Inner sheath - PVC/ HR PVC/ FRLS Zero Halogen and Outer sheath - PVC/HR PVC/FRLS. Complete in all respects.	45/mtr
168)	SITC of Havells Speaker Cable of 2 X 0.5 SQ. mm IND. 1.1 kV CABLE in recessed/surface in PVC conduit of suitable size (Havells transparent FR PVC insulated, twin core copper conductor (Flexible) Industrial Speaker cable).	55/mtr
169)	Supply, Installation ,Testing and commissioning of SITC of 1/3-INCH CMOS OR CCD digital color ip dome Poe network camera ,H.264 video .1080 P ,Tri-streaming : Dual H. 264 and M-jpeg simultaneously for lowlight situations with 3-9 mm vari-focal lens. Make: Bosch model NII-50022-V3	83,000.00
170)	Supply, Installation, Testing and commissioning of SITC of 1/3 inch CCD digital color bullet camera with outdoor ip 66housing and vari focal mega pixel lens Poe network camera , H.264 video .1080 P ,Tri-streaming : Dual H. 264 and M -jpeg	

	simultaneously for lowlight situations with 3-9 mm vari-focal lens. Make: Bosch model NTI-50022-V3	92,000.00
171)	Supply, Installation ,Testing and commissioning of 20x optical zoom range + 12x digital zoom with day/night outdoor 1080p full hd PTZ Auto dome outdoor camera ,Tri-streaming : dual H.264 video .1080 P ,Tri-streaming : Dual H. 264 and M -jpeg simultaneously for lowlight situations ,sector blanking ,99 presets,2 types of tour, pole mount . Make: Bosch (vG5-7220-epc4+vg4-A_PA2@3+ VG4_A_9541 )	2,87,000.00
172)	Supply, Installation ,Testing and commissioning of INDUSTRIAL GRADE 8 port Manageable POE network switch, layer 3 type with 2 Nos of SFP ports (SM/MM) and supports both SM/MM Fibre. complete in all respects. Make: allied, D-link, Cisco	<b>85,000.00</b>
173)	Purchase, Support and Installation of Bosch Camera Software license (Omnicast) for CCTV Surveillance System. complete in all respects.	15000/lic
174)	1 G- MULTIMODE FIBER DUBLEX SFP MODULE with following Features1 Gigabit bi-directional performance,Multi-mode Mini GBIC module operates at 850nm,Duplex LC connector,Maximum transmission distance of 550 meters, Use with OM2 fiber, ,Hot pluggable. complete in all respects. Make: Cisco, Allied, Legrand .	15,500.00
175)	Supply, laying, ,Testing and commissioning of full jacket armoured multimode/Single mode OFC cable to be laid at a depth of 2.5 feet in the steel/PVC/GI conduit/DLP trunking / DWC pipe with necessary connector ,etc. complete in all respects.	220/Mtr
176)	Splicing and Termination of multimode OFC cable of each core.	<b>400/ core</b>
177)	Supply and fixing of LC (Lucent Connector) and SC (Subscriber connector) cables (Fibre patch cords) of length upto 3 mtrs.	<b>1,050.00</b>
178)	Splicing and Termination box Tiffon type. The box must be dust and water proof. Complete in all respects	<b>550.00</b>
179)	Splicing and Termination box Bottle type. The box must be dust and water proof. Complete in all respects.	<b>850.00</b>
180)	Laying of OFC through Horizontal Directional Drilling including Single PLB (Duct of suitable size) at a suitable depth upto 1.5 mtrs including refilling of sand as required. Complete in all respects.	<b>550.00</b>
181)	Smoke Detector with built in LED, mounting base complete with all connection etc.	950/-
182)	Manual call boxes of MS Type in surface/recess with stainless steel chain & hammer assembly complete with glass and push button etc.	450/-
183)	SITC of high intensity weather resistant wailing type electronic hooter with sound output of 100-110 dB at 1 mtr , suitable for outdoor applications and suitable for operation on suitable DC supply (including batteries) whichever is needed including connections. Complete in all respects.	1850/-
184)	2 Zone fire alarm control panel as per IS: 2189 with backlit LCD Display. (Non addressable, conventional) <b>TECHNICAL SPECIFICATIONS:</b> Panel Operating Condition Operating Voltage AC Power 220v AC, 50Hz ± 10% Standby 24v DC Operating, Temperature 0°C to 40°C Operating Humidity 95% (non-condensing) Zone Operating Condition Normal Loop Voltage23v DC. Outputs Hooter Output1 A (24v DC) (Normal)NB Hooter output current can be increased as per customer requirement. <b>(Note: The panel be provided with batteries having atleast 6-8 hours backup time).</b> Complete in all respects.	15,500/-
185)	Supply,Installation,Testing and Commissioning of <b>50 Pair Telephone Junction box:</b> Capacity : <b>50 pairs</b> , Water proof performance IP45 level,frame plate, UV protection, Key lock or screw are choosable, Material of Construction: Steel, <b>Length: 380 mm,Width:300 mm, Height: 130 mm</b> , Technique :Cold Rolled , Modular telecom box: Designed to support the 237A IDC module Base and quick release cover included Base has ample provision for jumper rings etc ,50 pair LSA-PLUS@	5,500.00

	modules which contain a one piece contact providing a continuous link between wiring. The panel may be mounted on Galvanised Iron Stand of 2 feet above the ground. Make: Krone, ABS or Equivalent	
186)	Supply,Installation,Testing and Commissioning of <b>100 Pair Telephone Junction box with krone connectors:</b> Capacity : <b>100 pairs</b> , Water proof performance IP45 level,frame plate, UV protection, Key lock or screw are choosable, Material of Construction: Steel, Length: 380 mm,Width:300 mm, Height: 130 mm, Technique :Cold Rolled , Modular telecom box: Designed to support the 237A IDC module Base and quick release cover included Base has ample provision for jumper rings etc ,50 pair LSA-PLUS@ modules which contain a one piece contact providing a continuous link between wiring. The panel may be mounted on Galvanised Iron Stand of 2 feet above the ground. Make: Krone, ABS or Equivalent	9,500.00
187)	Supply,Installation,Testing and Commissioning of <b>20 Pair Telephone Junction box:</b> Capacity: 20 pairs, Water proof performance IP45 level, frame plate, UV protection, Key lock or screw are choosable, Material of Construction: Steel, Length: 380 mm,Width:300 mm, Height: 130 mm, Technique :Cold Rolled , Modular telecom box: Designed to support the 237A IDC module Base and quick release cover included Base has ample provision for jumper rings etc ,50 pair LSA-PLUS@ modules which contain a one piece contact providing a continuous link between wiring. Make: Krone, ABS or Equivalent	4,500.00
188)	Supply,Installation,Testing and Commissioning of <b>MDF Telephone Junction box/Pillar with krone connectors</b> : base for termination of 1000 telephone connections including providing of Krone modules and there bases termination of Capacity :1000 pairs, Water proof performance IP45 level,frame plate, UV protection, Key lock or screw are choosable, Material of Construction: Steel, Length: 380 mm,Width:300 mm, Height: 130 mm, Technique :Cold Rolled , Modular telecom box: Designed to support the 237A IDC module Base and quick release cover included Base has ample provision for jumper rings etc ,1000 pair LSA-PLUS@ modules which contain a one piece contact providing a continuous link between wiring. The panel may be mounted on Galvanised Iron Stand of 2 feet above the ground. Make: Krone, ABS or Equivalent .	25,000.00
189)	Supply, Installation, Testing and Commissioning of outdoor feeder panel with concrete base for termination of 1000 telephone connections including providing of Krone modules and there bases and <b>5 stage LED</b> integrated protection modules on 500 connections, Water proof performance IP45 level, frame plate, UV protection, Key lock or screw are choosable. The panel may be mounted on Galvanised Iron Stand of 2 feet above the ground. Complete in all respects.	1,35,000.00
190)	Supply, Installation ,Testing and commissioning of +48V 3.3A Industrial Switch Mode power supply( SMPS) with Aluminum casing, High quality. Compatible to layer 2 switches Input Voltage: 230V AC Power Rating: 240W Dimension : 215mm*114mm*49mm (L*W*H) MAKE: OMIRON,MEANWELL, ALLIED	6,000.00
191)	Complete Servicing and Testing of Air Circuit Breaker (ACB) of 420V, 1250A rating, including providing of Shunt Coils, Tripping coils and UV Coils. Complete in all respects.	15,500/-
192)	Servicing and Testing of 300kVAR Automatic Power Factor Correction (APFC) panel including changing of defunct and damaged Capacitors of suitable ratings.	10,000/-

	The job includes making the meters functional and all the parameters should be displayed. Complete in all respects.	
193)	Supply and fixing of 25kVAR heavy duty power capacitor for APFC Panel.(Neptune Ducati).	10,500/-
194)	Supply and fixing of 50kVAR heavy duty power capacitor for APFC Panel. (Neptune Ducati).	17,500/-
195)	Supply , Fixing and Testing of Remote Tap Changing Control (RTCC) panel. The job includes making the meter functional and all the parameters should be displayed. Complete in all respects.	34,500/-
196)	Complete Servicing and Testing of On-Line/On-Load Tap Changer (OLTC) panel of 1500kVA Transformer, changing of oil ( <b>Upto 150 ltrs of dehydrated oil</b> ) in OLTC tap changer tank, checking of oil level, WTI, OTI, proper functioning of Buchholz Relay, replacement of silica gel. Complete in all respects.	65,000/-
197)	Complete Servicing and Testing of HT/LT panel Meters including checking of proper functioning of Multi-Function meters, Master trip relays and other protection relays etc . Complete in all respects.	30,500/-
198)	Serving and Testing of 11kV vacuum Circuit Breaker (VCB). Complete in all respects.	28,500/-
199)	Supply and fixing of following items of 24V Dc, 240v Ac	
	a) Closing Release coils	4,700/-
	b) Shunt Release Coils	4,700/-
	c) Under-Voltage with time delay of 0-1-3-5 sec	9,500/-
195)	LT Panel Enclosure Outdoor type measuring 49”(h)x44”(w)x18”(d) made out of 1.6mm thick CRC sheet powder coated 49” (h) x 44” (w) x 18”(d) having front & back doors mounted on MS Angle Iron Pedestal of height 18” comprising of the following:	
Incomer:	Contactora 630A (AC3) TP with Wide Band Coil (Schneider Make) 2 No.	
	Auxiliary Contacts for above (2NO+2NC) (Schneider Make) 2 No.	
	Phase Sequence Relay (Minilec Make) 1 No.	
	On Delay Timer 240/415Vac (L&T Make) 1 No.	
	Selector Switch 2P 2W with Off (Salzer Make) 1 No.	
	Phase Indication Lamps 22.5mm 220Vac (R,Y,B) 3 Set.	
	MCB 6A SP 10kA (L&T Make) 1 No.	
Busbar	<b>TP Copper 630A</b> Mounted on DMC Busbar Supports and covered with heat shrinkable sleeves 1 Set.	2, 21,390.00
	Wire & Other Panel Accessories As required	
196)	LT Panel Enclosure Outdoor type measuring 49”(h)x44”(w)x18”(d) made out of 1.6mm thick CRC sheet powder coated 49” (h) x 44” (w) x 18”(d) having front & back doors mounted on MS Angle Iron Pedestal of height 18” comprising of the following:	
	Contactora 400A (AC3) TP with Wide Band Coil (Schneider Make) 2 No.	
	Auxiliary Contacts for above (2NO+2NC) (Schneider Make) 2 No.	
	Phase Sequence Relay (Minilec Make) 1 No.	
	On Delay Timer 240/415Vac (L&T Make) 1 No.	
	Selector Switch 2P 2W with Off (Salzer Make) 1 No.	
	Phase Indication Lamps 22.5mm 220Vac (R,Y,B) 3 Set.	
	MCB 6A SP 10kA (L&T Make) 1 No.	
	TP Copper 630A Mounted on DMC Busbar Supports and covered with heat Shrinkable sleeves 1 Set.	1,27,770.00

	Wire & Other Panel Accessories	As required	
197)	LT Panel Enclosure Outdoor type measuring 36”(h)x32”(w)x18”(d) made out of 1.6mm thick CRC sheet powder coated 36” (h) x 32” (w) x 18”(d) having front & back doors mounted on MS Angle Iron Pedestal of height 18” comprising of the following:		
	Contactors 300A (AC3) TP with Wide Band Coil (Schneider Make)	2 No.	98,900.00
	Auxiliary Contacts for above (2NO+2NC) (Schneider Make)	2 No.	
	Phase Sequence Relay (Minilec Make)	1 No.	
	On Delay Timer 240/415Vac (L&T Make)	1 No.	
	Selector Switch 2P 2W with Off (Salzer Make)	1 No.	
	Phase Indication Lamps 22.5mm 220Vac (R,Y,B)	3 Set.	
	MCB 6A SP 10kA (L&T Make)	1 No.	
	TP Copper 400A Mounted on DMC Busbar Supports and covered with heat		
	Shrinkable sleeves	1 Set.	
	Wire & Other Panel Accessories	As required	
198)	Supply, Installation , Testing and Commissioning of <b>Power Command Control panel PCC 3300 (Card Control Part No: A054J968)</b> for Cummins make 750kVA DG Set. Complete in All respects.		2,29,269/-
199)	Supply, Installation , Testing and Commissioning of <b>Display Control for Power Command Control Panel (Display Control Part No: 0300-6315-02)</b> for Cummins make 750kVA DG Set. Complete in all respects.		77,195/-
200)	Supply, Installation , Testing and Commissioning of <b>PCB ASSEMBLY DYNAMO GOV (Part No: 0327-1507)</b> for Cummins make 750kVA DG Set. Complete in all respects.		13,556/-

### 1. List of Approved Makes

S No.	Items/material	Approved Makes
1.	Wires/Cables.	Polycab / syska /Havells or equivalent
2.	Switches/sockets/Accessories.	Schneider/Legrand/L&T
3.	Ceiling Fan/Wall Fan/ Cabin Fan.	Havells/ Standard/Usha or equivalent
4.	MCB / Distribution Boards.	Schneider/ Legrand / L&T
5.	MCCB.	Schneider/ Legrand/L&T
6.	ACB/VCB.	Schneider/L&T/C&G
7.	Luminaries including CFL & LED lamp & Tubes Lights/Street Lights.	Philips / Havells / or equivalent.
8	LED Television/Smart Panels.	Sony/Samsung/Panasonic or equivalent
9	Telephone Cables.	Finolex/ Havells/Polycab or equivalent

**Head EE Department**